

DTIC FILE COPY

4

CR 89.005

NCEL

Contract Report

January 1989
An Investigation Conducted by
ABAM Engineers Inc., Federal Way, WA
Sponsored By Naval Facilities
Engineering Command

AD-A206 496

PRESTRESSED CONCRETE FENDER PILES: FENDER SYSTEM DESIGNS

ABSTRACT Designs for prestressed concrete fender piles for use at Navy piers in a wide range of fendering applications are presented. Two types of fender piles are discussed: an energy absorbing fender pile for use with camels and a reaction fender pile for use with foam-filled fenders.

Complete fender system designs incorporating either timber or steel wales with the baseline energy-absorbing prestressed concrete fender piles, as well as a new class of fender pile to resist the reaction from foam-filled fenders, are presented.

Design aids are given in the form of easy-to-use graphs. Design examples are also presented.

89

3

06

A

138

DTIC
ELECTE

06 MAR 1989

NAVAL CIVIL ENGINEERING LABORATORY PORT HUENEME, CALIFORNIA 93043

Approved for public release; distribution is unlimited.


METRIC CONVERSION FACTORS

Approximate Conversions to Metric Measures

Symbol	When You Know	Multiply by	To Find	Symbol
LENGTH				
in	inches	2.5	centimeters	cm
ft	feet	30	centimeters	cm
yd	yards	0.9	meters	m
mi	miles	1.6	kilometers	km
AREA				
in ²	square inches	6.5	square centimeters	cm ²
ft ²	square feet	0.09	square meters	m ²
yd ²	square yards	0.8	square meters	m ²
mi ²	square miles	2.6	square kilometers	km ²
	acres	0.4	hectares	ha
MASS (weight)				
oz	ounces	28	grams	g
lb	pounds	4.45	kilograms	kg
	short tons (2,000 lb)	0.9	tonnes	t
VOLUME				
tsp	teaspoons	5	milliliters	ml
Tbsp	tablespoons	15	milliliters	ml
fl oz	fluid ounces	30	milliliters	ml
c	cups	0.24	liters	l
pt	pints	0.47	liters	l
qt	quarts	0.95	liters	l
gal	gallons	3.8	liters	l
ft ³	cubic feet	0.03	cubic meters	m ³
yd ³	cubic yards	0.76	cubic meters	m ³
TEMPERATURE (exact)				
°F	Fahrenheit temperature	5/9 (after subtracting 32)	Celsius temperature	°C

Approximate Conversions from Metric Measures

When You Know	Multiply by	To Find	Symbol
LENGTH			
millimeters	0.04	inches	in
centimeters	0.4	inches	in
meters	3.3	feet	ft
meters	1.1	yards	yd
kilometers	0.6	miles	mi
AREA			
square centimeters	0.16	square inches	in ²
square meters	1.2	square yards	yd ²
square kilometers	0.4	square miles	mi ²
hectares (10,000 m ²)	2.5	acres	
MASS (weight)			
grams	0.035	ounces	oz
kilograms	2.2	pounds	lb
tonnes (1,000 kg)	1.1	short tons	
VOLUME			
milliliters	0.03	fluid ounces	fl oz
liters	2.1	pints	pt
liters	1.06	quarts	qt
liters	0.26	gallons	gal
cubic meters	35	cubic feet	ft ³
cubic meters	1.3	cubic yards	yd ³
TEMPERATURE (exact)			
Celsius temperature	9/5 (then add 32)	Fahrenheit temperature	°F



*1 in = 2.54 (exactly). For other exact conversions and more detailed tables, see NBS Misc. Publ. 286, Units of Weights and Measures, Price \$2.25, SD Catalog No. C13 10 286.

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER CR 89.005	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Prestressed Concrete Fender Piles: Fender System Designs		5. TYPE OF REPORT & PERIOD COVERED Final Sep 1987 - Aug 1988
7. AUTHOR(s)		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS ABAM Engineers Inc. 33301 Ninth Ave South Federal Way, WA 98003-6395		8. CONTRACT OR GRANT NUMBER(s) N62474-84-C3140
11. CONTROLLING OFFICE NAME AND ADDRESS Naval Civil Engineering Laboratory Port Hueneme, CA 93043-5003		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS Y1316-001-02-010
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Naval Facilities Engineering Command 200 Stovall Street Alexandria, VA 22332-2300		12. REPORT DATE January 1989
		13. NUMBER OF PAGES 78
		15. SECURITY CLASS (of this report) Unclassified
		15a. DECLASSIFICATION DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution is unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) prestressed concrete, concrete, fenders, piles, fender piles.		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) → Designs for prestressed concrete fender piles for use at Navy piers in a wide range of fendering applications are presented. Two types of fender piles are discussed: an energy absorbing fender pile for use with camels and a reaction fender pile for use with foam-filled fenders. Complete fender system designs incorporating either timber or		

DD FORM 1 JAN 73 1473 EDITION OF 1 NOV 65 IS OBSOLETE

Unclassified
SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

684
Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

steel wales with the baseline energy-absorbing prestressed concrete fender piles, as well as a new class of fender pile to resist the reaction from foam-filled fenders, are presented.

Design aids are given in the form of easy-to-use graphs. Design examples are also presented. *Review*

Unclassified


SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

TABLE OF CONTENTS

<u>Section</u>		<u>Page</u>
1	SUMMARY	1-1
2	INTRODUCTION	2-1
3	FENDER SYSTEMS DESIGN AND DETAILING	3-1
4	REACTION FENDER PILE DESIGN	4-1
	4.1 Introduction	4-1
	4.2 Design Criteria	4-2
	4.3 Pile Reinforcing Configuration	4-2
5	REACTION FENDER PILE DESIGN AIDS	5-1
	5.1 Purpose of Design Aids	5-1
	5.2 Theory and Development	5-2
	5.3 Design Aid Figures	5-3
	5.4 Design Procedure	5-3
	REFERENCES	R-1
	NOTATIONS	N-1
 <u>Appendix</u>		
A	DRAWINGS	A-1
B	CALCULATIONS	B-1

LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
5.1	24" Square Reaction Pile with $f'_c = 8000$ psi	5-5
5.2	24" Square Reaction Pile with $f'_c = 7000$ psi	5-6
5.3	24" Square Reaction Pile with $f'_c = 6000$ psi	5-7



SECTION 1

SUMMARY

The Department of the Navy, through the Naval Civil Engineering Laboratory (NCEL) at Port Hueneme, California, has initiated a program to develop prestressed concrete fender piles for use at Navy piers in a wide range of fendering applications. This report completes the design portion of the multiphase testing, analysis, and design effort [1.1].

Two types of fender piles are discussed in this report: an energy-absorbing fender pile for use with camels and a reaction fender pile for use with foam-filled fenders.

Complete fender system designs incorporating either timber or steel wales with the baseline energy-absorbing prestressed concrete fender piles are presented. The system designs were developed from conceptual studies performed in Phase IV of this study [1.2].

Design of a new class of fender pile to resist the reaction from foam-filled fenders is presented. Design criteria and design aids were developed for a 24-in.-square prestressed precast concrete pile with concrete strengths of 6000, 7000, and 8000 psi. The design aids are in the form of easy-to-use graphs. A design example is also presented.

As a result of this phase, detailed drawings of complete fender systems and design aids for a new class of fender pile are available to assist in procuring precast prestressed concrete fender pile systems for Navy facilities.

SECTION 2

INTRODUCTION

To encourage and promote the use of energy-absorbing precast concrete fender piles it is necessary to develop system details that may be used by engineers to incorporate them into complete designs. The systems presented herein are very similar to those used at existing Navy facilities. The details are also prepared with the thought in mind that these fender piles can be adapted to existing timber or steel fender systems without significant changes to existing chock and wale systems. The fender systems are discussed in Section 3.

The concrete reaction fender piles serve to transfer the reactions from a foam-filled fender into the pier or wharf and harbor bottom. Energy absorption of a foam-filled fender is sufficient in itself. Energy absorption by the concrete piles adds to the system overload capacity. In an effort to minimize costs yet provide the necessary performance and durability requirements established in previous phases and to make more efficient use of the prestressed concrete piles as reaction piles, the design criteria developed in previous phases were reevaluated. The reaction fender piles selected are discussed in Section 4.

SECTION 3

FENDER SYSTEMS DESIGN AND DETAILING

The two fender system designs presented in this report employ the prototype energy-absorbing concrete fender pile that was developed in previous phases of the study. The standard pile is 18 in. square and is prestressed with twenty 1/2-in.-diameter strands in a rectangular pattern. Depending on the site-specific conditions and the required system energy, a different size pile could be used. For more specific information on the pile design itself, refer to Phase III of this study [3.1].

The drawings for the fender pile systems are contained in Appendix A. Two schemes are presented: Alternate 1 uses timber wales and Alternate 2 incorporates a steel W-section wale. The timber wale system will be less expensive initially than the steel wale and long-term maintenance for the timber wale will be less.

The assumptions used in developing the fender system alternates are

- The berthing energy of the ship is absorbed entirely by the concrete fender pile.
- The fender pile is contacted by the ship only at the water line and not at the top of the pile. This requires either a log camel or some other type of floating separator between the ship and the pile. (A partial detail is provided for use when this assumption is not met.)
- The system details are developed for new facility construction but can be easily adapted to existing facilities.

The system elements common to both alternates are listed below:

- Timber chocks
- No rub strip on the pile face
- Pile spacing = 8 ft

Following is a discussion of critical components of the system and their purpose:

The fender system is designed so that the fender piles absorb all the berthing energy; therefore, rubber fenders behind the piles at the deck level are not required. Rubber fenders are needed when the pile acts as a "reaction pile" and transfers the berthing force up to the pile top and into the rubber fender, which in turn absorbs the energy. Rubber fenders would also be required if a camel or separator were not used to berth a ship, and the ship contacted the pile top directly.

In the case where the fender pile absorbs the energy and the rubber fender is omitted, the fender system (i.e., wale and chock) can be supported directly off the pier rather than off the fender piles. The fender pile is then held against the chock and wale with a restraining strap. The advantage of this system is that if some piles are broken, the remaining fender system has not lost its vertical support.

The pile is held against the wale using a steel strap that projects slightly beyond the face of the pile. Should a vessel berth directly against the top of the pile, consideration should be given to protecting the vessel and strap. There also would be no energy absorption possible in the system. This emphasizes the need for a camel or separator. It may be advantageous to project the chock beyond the face of the pile to prevent ship contact with the steel strap, which could damage both the ship paint and strap around the pile.

A method of attaching the wale to the pier is presented in the drawings. A T-bolt insert is cast in the face of the concrete pier. The 1-in.-diameter T-bolt can then be installed and rotated 90 degrees and locked in place. The holes for both the blocking and the wale should be drilled

based on the as-built location of the T-bolts. Other options for attaching the wale to the pier include screw anchors, coil bolts, and drill and epoxy bolts in the pier face. Anchor bolts could also be cast in the pile cap or bullrail with the ends projecting out. This may not be as desirable because it requires holes to be drilled in the side of the formwork.

The T-bolt or other connector that supports the wales must be properly tightened. The longitudinal forces that may be imparted to the fender system due to berthing must be resisted by both friction between the wale and blocking, and the blocking and pier. The component of longitudinal force normal to the pier increases the friction resistance of the fender system. The shear capacity of the bolt alone is small due to the fact that the blocking behind the wale may allow bending in the bolt if the friction force is overcome.

The purposes of the blocking between the pier and the wale is to provide a means to adjust for irregularities in the bullrail. This offset also provides access to the bolts that connect the chock and wale together and the wale splices. The blocking could be either solid rubber or timber.

Another possible option is to omit the wale and attach the chock and pile and blocking directly to the pier face with through bolts and screw anchors. This option is less desirable than methods previously described because field drilling of the precast prestressed concrete pile may be required in order to line up with the screw anchors.

If rubber fenders are used between the wale and the pier, the wale is usually designed to distribute the reaction from the pile top into several rubber fenders. When a solid block is used behind the wale in place of the rubber fender, there is no distribution of force. In this case the wale and blocking provide a standoff between the pier and pile. The minimum standoff might be controlled by the ability of the pile driving equipment to drive close to the pier. There might also be a minimum distance required between the outboard support pile of the pier

structure and the fender pile. The timber wale is shown as two pieces rather than one large piece but either option may be used. The type of timber wale used will depend on regional timber availability and costs.

The purpose of the chock is to restrain the pile from moving along the pier face and to keep it from twisting in plan. To accomplish this, the timber chocks should be cut for a tight fit. Because of their short length, the chocks are to be one-piece units.

The chock and wale are designed to support personnel walking on the fender system. If it is necessary to support additional live load (cables, steam lines, etc.), the connection of the wale to the pier should be reevaluated.

For the timber wale alternate system design with rubber fenders behind the head of each pile, the fender system is attached directly to the pile. The pile is then held against the pier by a chain that connects to a steel hardware unit cast into the pier. The most positive method of attaching the chock/wale to the pile is to use a through bolt. The detail for the through bolt requires more accurate driving tolerances than the steel strap does. The through bolt also presents more of a fabrication problem because of the number of strands in the pile. In order to resist the longitudinal forces, a set of horizontal chains is required at certain intervals to transfer the force from the wale into the pier.

SECTION 4

REACTION FENDER PILE DESIGN

4.1 INTRODUCTION

Foam-filled fenders are used extensively in the Navy for both absorbing the energy due to ship berthing and as a standoff between the ship and the pier structure when the ship is moored. Currently, there are many different methods of transferring the reaction of the foam-filled fender to the pier structure. In Phase IV of this study [1.2], different concepts were presented using a 24-in.-square prestressed concrete fender pile as a reaction pile behind a 6-ft-diameter by 12-ft-long foam-filled fender. The purpose of this section of the report is to develop design criteria and design aids for the 24-in.-square pile as a continuation of the previous phase.

The foam-filled fender is assumed to absorb all the required energy from ship berthing. The reaction associated with the berthing energy is transmitted through the foam-filled fender either directly into the concrete reaction piles, or into a bearing panel to help distribute the loads to the piles. The actual contact length over which the foam-filled fender will deliver the reaction force must be taken into account.

The pile is designed as a "stiff" member, transferring the reaction from the foam-filled fender into the pier and harbor bottom. The design includes a higher level of prestress force with fewer strands than did the "soft" pile, whose primary purpose was to absorb energy, not to transfer a reaction. The "stiff" design results in a more economical pile to resist a reaction force than the "soft" pile but it does not have the energy absorption capability.

4.2 DESIGN CRITERIA

The horizontal force on the pile due to the foam-filled fender reaction could result from a static or dynamic force. The static force could be from either wind or current. The dynamic force would result from berthing the vessel. Regardless of the origin of the force, it must be factored to obtain an ultimate load (versus a working load) to be used in the reaction pile design.

The energy absorbed by the "stiff" pile is not counted on in the design. For static loads, energy is not a design parameter and for dynamic loads the foam-filled fender is assumed to absorb all the energy. Therefore, energy absorbed by the pile is not critical but adds to the overload capacity.

The "effective" number of concrete piles required to resist the ultimate reaction force is not necessarily the number of piles that must be provided. The word effective is used because the designer must calculate the actual distribution of load to each pile. The "system design" is analogous to a beam on elastic foundation, which may result in some piles being more heavily loaded than others. If a bearing panel is required, the load distribution also changes. The pile loaded with the highest reaction in the system will control the design. See the previous phase of this study for items to be considered [1.2].

4.3 PILE REINFORCING CONFIGURATION

The pile is designed as a vertical flexural member, not a compression column. The "stiff" pile concept developed in the previous phase was chosen over the "soft" pile concept. For details of the design, refer to the previous phase of this study. The design drawing for the 24-in.-square reaction pile is found in Appendix A. A total of twenty-eight 1/2-in. strands are used along with No. 3 confining steel.

SECTION 5

REACTION FENDER PILE DESIGN AIDS

5.1 PURPOSE OF DESIGN AIDS

Design aid figures (Figures 5.1, 5.2, and 5.3) are presented to assist the designer in selecting the number of "effective" piles required to resist the reaction from a foam-filled fender or other marine fendering unit. This report addresses the design problem from the point of knowing the maximum factored force imparted by the fender into the pile.

The issue of what design criteria should be used to design the marine fendering unit is beyond the scope of this report, but must be dealt with in the context of arriving at the factored loads. The derivation of the maximum factored force applied to the pile due to wind, current, and ship berthing is also beyond the scope of this study. The important requirement for designing the concrete reaction piles is that the loads must be factored loads, not working loads.

Some general points to be considered are

- The designer must calculate the factored (or ultimate) loads for both wind plus current and berthing.
- If the maximum factored loads are close to the maximum rated reaction of the marine fendering unit, use the rated reaction for the reaction pile design.
- If a larger fender than required by reaction design is used to provide a standoff between the ship and pier, and the actual factored loads are much smaller than the rated reaction of the fender, use the maximum factored load for the reaction pile design.

- Consideration should be given to the tolerances allowed by Military Specifications [5.1] for the maximum rated reaction when using the rated loads.

5.2 THEORY AND DEVELOPMENT

When using the design figures to select the number of reaction piles required, the design load must be considered as a factored ultimate load and not a service level load. Military Handbook 1025/1 [5.2] gives guidelines for the ultimate load factors to be used. Figures 5.1, 5.2, and 5.3 present plots of the "design strength load capacity" versus the "design span length" of the piles.

The pile load capacity is limited by the moment capacity of the section for a given concrete strength when loaded no closer than 6 ft from the support. This 6-ft dimension is based on the assumption that the top of the pile extends a minimum of 1 ft beyond the support. When the pile is loaded closer than 6 ft, the load capacity should be calculated. Load capacity will be limited by either the shear capacity of the section or a reduced moment capacity due to the strand development length available.

The controlling moment capacity in the pile is defined as "the moment at which the extreme fiber concrete compressive strain is equal to 0.0021 in./in. if the maximum strand stress is less than 240 ksi." Piles similar to the reaction piles have been load tested and shown to perform well under cyclic loads producing the above-mentioned strain. In lieu of taking the ultimate capacity of the pile at the design code strain limit of 0.003 in./in. and multiplying it by a strength reduction factor (ϕ), we have chosen the moment at this lower strain as the ultimate factored capacity.

The moment capacity of the pile is constant for a given concrete strength, and does not depend on pile length or load location for loads applied greater than 6 ft from the support. The corresponding reaction is a function of this moment capacity and varies with pile span length

and load location. The corresponding pile reaction into the pier can be calculated by statics and is equal to the shear in the upper portion of the pile. This reaction should be used to check the strength of the existing or new wharf to accommodate the fender reaction.

5.3 DESIGN AID FIGURES

The figures developed in this report are intended for pile support lengths varying from 40 to 90 ft. The range of pile load locations ranges from 6 to 25 ft below the top support. Plotted on the charts are nominal load capacity curves for particular load locations versus pile support lengths. The three charts provided are for concrete strengths (f'_c) equal to 8000, 7000, and 6000 psi and are used to calculate the "effective" number of piles.

5.4 DESIGN PROCEDURE

The procedure to select the number of effective piles follows:

Step 1

- a) Determine the pile span length, L_e .
- b) Determine the maximum and minimum value of "a," which depends on where the reaction from the foam-filled fender or other marine fendering unit will contact the concrete pile due to tidal variations or other factors (i.e., the fender may also be hung from the structure rather than floating).
- c) Choose the pile concrete strength, f'_c , and refer to the appropriate figure.

Step 2


Determine the maximum rated reaction that results when the foam-filled fender is at 60% compression. This criterion may vary for other types of marine fendering. This will be treated as the ultimate load. Check that the factored loads due to wind, current, and berthing are less than the foam-filled fender rated reaction. Refer to Section 5.1 for further explanation.

Step 3

Knowing the pile span length, extend a vertical line up through the two extreme load locations. Follow the intersection of the lines horizontally and read the pile reaction capacity.

Step 4


The "effective" number of reaction piles required is equal to the ultimate load divided by the smallest pile capacity found in Step 3.



SCALE: HORIZ 1"=10'-0"
VERT 1"=20 KIPS

NOTE: FOR $a < 6'$
SEE REPORT


FIGURE 5.1, 24" SQUARE REACTION PILE
WITH $f'_c = 8000 \text{ psi}$



SCALE: HORIZ 1"=10'-0"
VERT 1"=20 KIPS

NOTE: FOR $a < 6'$
SEE REPORT

FIGURE 5.2, 24" SQUARE REACTION PILE
WITH $f'_c = 7000 \text{ psi}$




SCALE: HORIZ 1"=10'-0"
VERT 1"=20 KIPS

NOTE: FOR $a < 6'$
SEE REPORT

FIGURE 5.3, 24" SQUARE REACTION PILE
WITH $f'_c = 6000 \text{ psi}$

DESIGN EXAMPLE

STEP 1



- $L_e = 15' + (+50') = \boxed{65'}$
- a VARIES, RANGES FROM :
 MINIMUM $a = 15' - 5' = \boxed{10'}$
 MAXIMUM $a = 15' - 0' = \boxed{15'}$
- SPECIFY THE 28 DAY STRENGTH OF THE CONCRETE PILE AS $f'_c = 8000 \text{ psi}$. THEREFORE USE
 DESIGN AID FIGURE 5.1

STEP 2 CALCULATE THE MAXIMUM FACTORED FORCE ON THE REACTION FENDER PILE FROM THE FOAM FILLED FENDER.

⇒ GIVEN: $P_u = 200$ Kips

STEP 3 DETERMINE THE NOMINAL PILE LOAD CAPACITY USING FIGURE 5.1.

a) EXTEND A LINE UP VERTICALLY FROM THE KNOWN SPAN LENGTH,

⇒ $L_e = 65$ FEET

b) FIND THE INTERSECTION WITH THE LARGER "a" VALUE DETERMINED IN STEP 1.b,

⇒ $a = 15$ FEET

c) EXTEND THE LINE OVER HORIZONTALLY AND READ THE NOMINAL PILE LOAD CAPACITY,

⇒ $\phi P_n = 67.5$ Kips


STEP 4 CALCULATE THE NUMBER OF "EFFECTIVE" PILES REQUIRED. SEE SECTION 5 OF REPORT FOR DEFINITION.

NUMBER OF "EFFECTIVE PILES" = $N =$

$$\frac{P_u}{\phi P_n}$$

⇒ $= \frac{200}{67.5} = 2.96$, SAY $N = 3$ PILES

CAUTION: CALCULATE REACTION AT TOP OF PILE AND CHECK AGAINST STRENGTH OF PIER OR WHARF.



SCALE: HORIZ 1"=10'-0"
VERT 1"=20 KIPS

NOTE: FOR $a < 6'$
SEE REPORT

FIGURE 5.1, 24" SQUARE REACTION PILE
WITH $f'_c = 8000 \text{ psi}$

REFERENCES





- 1.1 Naval Facilities Engineering Command. Test and Evaluation Master Plan: Development of Prestressed Concrete Fender Piles, Program Element 63725N, Project No. Y0995-SL. Alexandria, VA, June 1984.
- 1.2 Naval Civil Engineering Laboratory. Contract Report. Prestressed Concrete Fender Piles: Fender System Designs. ABAM Engineers Inc., Federal Way, WA, February 1988.
- 3.1 Naval Civil Engineering Laboratory. Contract Report CR 88.003: Prestressed Concrete Fender Piles - Final Designs (NCEL Contract No. N62474-86-C-7268). ABAM Engineers Inc., Federal Way, WA, December 1987.
- 5.1 Military Specification. Fenders, Marine, Foam Filled, Netless. MIL-F-29248(YD), 21 November 1986.
- 5.2 Military Handbook. Piers and Wharves. MIL HDBK-1025/1, 30 October 1987.

NOTATIONS

a	Distance from support at pile top to location of load application
f'_c	Specified compressive strength of concrete
L_e	Pile design span length calculated from centerlines of supports
N	Effective number of piles
P_n	Nominal load capacity of pile
P_u	Factored (ultimate) force applied to pile from reaction of marine fendering unit
ϕ	Strength reduction factor
ϕP_n	Design strength load capacity of pile

**APPENDIX A
DRAWINGS**


CONCRETE INVERT
 10' 0" BELOW
 10' 0" BELOW
 10' 0" BELOW



[illegible]




CONCRETE INSERT
 10" TEE BOLT
 W/ C.P. INSERT
 OR EQUAL, TYP.



10" ROD
 SEE 5-2

2
 5-2

PLAN
 SCALE: 3/4" = 1'-0"



1
 5-2

10" BOLT W/ DOUBLE NUT
 SEE 4-2

2x2 TIMBER CHOCK

8" SQUARE P.C. PILE

1
 5-2

SCALE: 1/4" = 1'-0"

EMBEDMENT LENGTH
 PER GEOTECHNICAL
 RECOMMENDATIONS



5
 5-2


SECTION
 SCALE: 1/4" = 1'-0"

6
 5-2


SECTION
 SCALE: 1/4" = 1'-0"

[illegible]

MARK 'DRIVING END'
ON TOP SURFACE
BURN STRANDS
FLUSH WITH
PILE TIP




24" PRESTRESSED CONCRETE PILE
NTS



2 PILE SECTION
1'-0"=1'-0"

STRESS
PILE SIZE
CONCRETE AREA
TENSIONING UN
INITIAL PRESTI
DESIGN PRESTRI
DESIGN CONCRE



NOTES:

1. THIS PRESTRESSED CONCRETE PILE IS DESIGNED AS A REACTION PILE VERSUS A FENDER PILE. A REACTION PILE TRANSFERS FORCES WHEREAS A FENDER PILE ABSORBS ENERGY.
2. LIFTING DEVICE LOCATIONS ARE TO BE DETERMINED BY THE FABRICATOR CONSIDERING HANDLING STRESSES AND DRIVING REQUIREMENTS.
3. PRECAST CONCRETE PILES
F'C = PSI AT 28 DAYS
4. CONCRETE STRENGTH AT PRESTRESS TRANSFER, 3500 PSI MINIMUM.
5. REINFORCEMENT
A. REBAR: ASTM A615, GR 60
B. PRESTRESSING STEEL: 1/2" Ø, 270 KSI SEVEN WIRE, UNCOATED, STRESS RELIEVED OR LOW RELAXATION STRANDS PER ASTM A4 6.
6. MARK EACH END OF PILE AS SHOWN.
7. SEE SPECIFICATIONS FOR ADDITIONAL PILE FABRICATION REQUIREMENTS.

STRESSING DATA	
PILE SIZE	24" x 24"
CONCRETE AREA	576 IN ²
TENSIONING UNITS	28 STRANDS
INITIAL PRESTRESS FORCE	810 KIPS
DESIGN PRESTRESS FORCE	660 KIPS
DESIGN CONCRETE STRESS	1145 PSI

IF SHEET IS LESS THAN 28"x40", SHEET HAS BEEN REDUCED. USE GRAPHIC SCALE.

NCEL 88-8-3F		DEPARTMENT OF THE NAVY		NAVAL FACILITIES ENGINEERING COMMAND	
DATE: BY: CHECKED BY: DATE: DESIGNED BY: DATE: DRAWN BY: DATE: S.I.C. FILE NO. NO. S.I.C.		PRESTRESSED CONCRETE REACTION PILE 24" SQUARE PILE			
DATE/ACTIVITY TO: DATE: TITLE: DATE: APPROVED: DATE:		S.I.C. CODE REPT. NO. NAVAL BUILDING NO. F 80091 CHECKED BY: DATE: SCALE: AS NOTED SPEC: DESIGNED BY:			

APPENDIX B
CALCULATIONS

Project NCEL Phase II

Subject _____

Sheet _____ of _____

Job No. _____

Designer _____

Date 8/31/89

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
Reinforcing design	1
Pile design criteria	7
Shear capacity	10
Strand development	15
24" ϕ Pile Design aids	17
Equivalent ϕ factor and computer runs	28

Project NCEC Phase II

Subject Pile Reinforcing

Sheet 1 of 34

Job No. _____

Designer CWS

Date 6/6/93

Size $24 \times 24 = 576 \text{ in}^2$

Prestress level $\pm 1150 \text{ psi}$

Find number of strands & stress, f_{se}

$$\text{Force} = \frac{1150 \text{ psi} \times 576 \text{ in}^2}{1000} = 662 \text{ kips}$$

$$f_{se} = \frac{P}{A} = \frac{662 \text{ k}}{N = .153}$$

<u>N</u>	<u>f_{se} (ksi)</u>	
20	216	} Too high
24	180	
28	155	← Ideal, use !
32	135	} Too low
36	120	
40	108	

Check Concrete Tension

Per DM 25.1, sec. 5.4.4.3 c)

Allowable stresses for concrete

Must satisfy one of two criteria:

1) Tension stress $\leq 12\sqrt{f'_c}$

$P/A = 1.145 \text{ ksi}$

$M/S = \frac{778.4 \text{ ft-k} \times 12 \text{ in}}{24(24)^2/6} = 4.05 \text{ ksi}$

$12\sqrt{f'_c} = 12\sqrt{8000}/1000 = 1.07 \text{ ksi}$

$P/A - M/S = 1.145 - 4.05 = \underline{2.91} > 1.07 \quad \underline{\underline{NG!}}$

2) If concrete member is designed specifically for energy absorption do not have to conform to the above requirements.

Since this pile has been tested to perform in bending, it does not have to conform to the above tension requirement. Pile is okay

PROJECT: NCEL FENDER SYSTEM STUDY W/ 24" PILES
 DATE: 12/1/87
 DESIGNER: CWS
 PROGRAM: 'FENDER' DEVELOPED BY ABAM ENGR. INC.

2-3-84

Used

DATA FILE: B+24PILE2
 PILE NUMBER: 24" SQ. W/ RECTANGULAR STRAND PATTERN
 REVISION #: 0
 REMARKS: 28 STRANDS W/ 8/6/0 PAT.

PILE DIMENSIONS:

LENGTH = 65 ft
 LOAD FROM TOP = 15 ft
 DEPTH = 24 in
 WIDTH = 24 in

Stiff

CONCRETE DATA:

STRENGTH f'_c = 8 ksi
 MODULUS E = 4527 ksi
 PRESTRESS f_{pc} = 1145 psi

STRAND DATA:

STRAND TYPE = LOW RELAXATION
 # STRANDS = 28
 STRESS f_{pu} = 270 ksi
 STRESS f_{se} = 154 ksi
 MODULUS E = 28000 ksi

AREA = 1.224 sq.in
 AREA = .918 sq.in
 AREA = 0 sq.in
 AREA = 0 sq.in
 AREA = .918 sq.in
 AREA = 1.224 sq.in

DEPTH = 2.75 in
 DEPTH = 4.75 in
 DEPTH = 6.75 in
 DEPTH = 17.25 in
 DEPTH = 19.25 in
 DEPTH = 21.25 in

MOMENT M_n (k-ft)	CURVATURE (rad/in)	CONC STRAIN (in/in)	UPPER STRAND STRESS (ksi)	LOWER STRAND STRESS (ksi)	NA DEPTH (in)
234.8	2.085E-05	0.00050	-148.6	-159.4	24.00
374.4	4.053E-05	0.00070	-144.5	-165.5	17.27
466.3	6.578E-05	0.00090	-140.9	-174.9	13.68
541.3	9.559E-05	0.00110	-137.6	-187.1	11.51
610.3	1.290E-04	0.00130	-134.5	-201.4	10.08
676.5	1.654E-04	0.00150	-131.7	-216.9	9.07
725.5	2.032E-04	0.00170	-129.1	-227.9	8.36
756.8	2.415E-04	0.00190	-126.4	-235.2	7.87
778.4	2.803E-04	0.00210	-123.8	-240.4	7.49
794.2	3.194E-04	0.00230	-121.2	-244.3	7.20
806.2	3.588E-04	0.00250	-118.6	-247.4	6.97
815.7	3.986E-04	0.00270	-116.1	-249.8	6.77
823.4	4.387E-04	0.00290	-113.6	-251.7	6.61
826.8	4.589E-04	0.00300	-112.3	-252.6	6.54

DATA FILE: B:24PILE2
PILE NUMBER: 24" SQ. W/ RECTANGULAR STRAND PATTERN
REVISION #: 0
REMARKS: 28 STRANDS W/ 8/6/0 PAT.

MOMENT Mn (k-ft)	CONC STRAIN (in/in)	ENERGY (k-ft)	LOAD (kips)	DEFLECTION (in)
234.8	0.00050	0.6	20.3	0.8
374.4	0.00070	2.0	32.5	1.4
466.3	0.00090	3.7	40.4	1.9
541.3	0.00110	6.1	46.9	2.6
610.3	0.00130	9.2	52.9	3.3
676.5	0.00150	13.3	58.6	4.2
725.5	0.00170	17.1	62.9	5.0
756.8	0.00190	20.2	65.6	5.5
778.4	0.00210	22.8	67.5	6.0
794.2	0.00230	25.1	68.8	6.4
806.2	0.00250	27.2	69.9	6.8
815.7	0.00270	29.0	70.7	7.1
823.4	0.00290	30.7	71.4	7.4
826.8	0.00300	31.5	71.7	7.5

PROJECT: NCCL FENDER SYSTEM STUDY W/ 24" PILES
 DATE: 11/11/87
 DESIGNER: CWS
 PROGRAM: 'FENDER' DEVELOPED BY ABAM ENGR. INC.

11/11/87

Used

DATA FILE: R:24PILE.DAT
 PILE NUMBER: 24" SQ. W/ RECTANGULAR STRAND PATTERN
 REVISION #: 0
 REMARKS: 36 STRANDS W/ 10/8/0 PAT. 1/2" ϕ

PILE DIMENSIONS:

LENGTH = 65 ft
 LOAD FROM TOP = 15 ft
 DEPTH = 24 in
 WIDTH = 24 in

CONCRETE DATA:

STRENGTH f'_c = 8 ksi
 MODULUS E = 4577 ksi
 PRESTRESS f_{pc} = 599 psi

STRAND DATA:

STRAND TYPE = LOW RELAXATION
 # STRANDS = 36
 STRESS f_{pu} = 270 ksi
 STRESS f_{se} = 62.745 ksi
 MODULUS E = 29000 ksi

AREA = 1.53 sq.in DEPTH = 2.75 in
 AREA = 1.224 sq.in DEPTH = 4.75 in
 AREA = 0 sq.in DEPTH = 6.75 in
 AREA = 0 sq.in DEPTH = 17.25 in
 AREA = 1.224 sq.in DEPTH = 19.25 in
 AREA = 1.53 sq.in DEPTH = 21.25 in

Soft

MOMENT M_n (k-ft)	CURVATURE (rad/in)	CONC STRAIN (in/in)	UPPER STRAND STRESS (ksi)	LOWER STRAND STRESS (ksi)	NA DEPTH (in)
125.2	1.092E-05	0.00026	-59.9	-65.6	24.00
157.2	1.429E-05	0.00030	-59.1	-66.5	21.00
263.6	3.221E-05	0.00050	-55.4	-75.2	13.09
342.1	6.961E-05	0.00070	-52.2	-82.2	10.06
418.0	1.054E-04	0.00090	-49.3	-103.9	8.54
495.0	1.438E-04	0.00110	-46.7	-121.2	7.66
573.4	1.837E-04	0.00130	-44.2	-139.3	7.09
652.8	2.246E-04	0.00150	-41.7	-158.1	6.66
725.0	2.639E-04	0.00170	-39.1	-175.8	6.44
787.7	3.004E-04	0.00190	-36.3	-192.0	6.32
843.7	3.348E-04	0.00210	-33.4	-206.8	6.27
893.3	3.681E-04	0.00230	-30.4	-219.7	6.25
933.6	4.020E-04	0.00250	-27.4	-228.5	6.22
965.0	4.373E-04	0.00270	-24.5	-235.0	6.17
988.7	4.743E-04	0.00290	-21.7	-240.0	6.11
998.3	4.933E-04	0.00300	-20.4	-242.1	6.06

DATA FILE: B:24PILE.DAT
 PILE NUMBER: 24" SQ. W/ RECTANGULAR STRAND PATTERN
 REVISION #: 0
 REMARKS: 36 STRANDS W/ 10/8/0 PAT. $\frac{1}{2}" \phi$


MOMENT Mn (k-ft)	CONC STRAIN (in/in)	ENERGY (k-ft)	LOAD (kips)	DEFLECTION (in)
125.2	0.00026	0.2	10.8	0.4
157.2	0.00030	0.3	13.6	0.5
263.6	0.00050	1.3	22.8	1.2
342.1	0.00070	3.0	29.6	1.9
418.0	0.00090	5.6	36.2	2.9
495.0	0.00110	9.4	42.9	4.0
573.4	0.00130	14.2	49.7	5.3
652.8	0.00150	20.1	56.6	6.6
725.0	0.00170	26.4	62.8	7.9
787.7	0.00190	32.7	68.3	9.0
843.7	0.00210	38.9	73.1	10.1
893.3	0.00230	45.0	77.4	11.1
933.6	0.00250	50.4	80.9	11.9
965.0	0.00270	55.2	83.6	12.6
989.7	0.00290	59.3	85.7	13.2
998.3	0.00300	61.1	86.5	13.4

$$\frac{2}{3} \times 61.1 = 40.7 > 38.9$$

Criteria for Pile Design / Use of Table

Basic design criteria assumptions:

- 1) These piles are used to resist the reaction from foam-filled fenders.
- 2) The types of forces resisted are
 - a) Wind & current forces
 - b) Reaction associated with energy absorption of foam filled fender due to berthing
- 3) Use Navy Design Manual DM25.1 for design criteria.
 - a) Load Factors 1.25 Wind & current - US
 1.7 Berthing - U2
 Sec. 3.4
 - b) The fender system must be able to absorb 50% more energy than calculated in the DM for a accidental case. The fender system must provide this capacity.
- 4) The pile design aids are based on the nominal strength of the pile; therefore, they are to be checked with ultimate loads and not working loads.
- 5) Foam filled fender for design is $6' \phi \times 12'-0"$
 $P_u(\text{min}) = 186^k$



Project WGL Phase II


Sheet 7 of 34

Job No. _____

Subject Design Criteria

Designer CWJ

Date 6/15/93



Shear

ACI Eqn(11-3)

$$V_c = 2\sqrt{f'_c} b d = 82.4 \text{ k}$$

$$V_s = 84.5 \text{ k}$$

$$\phi V_n = .85 (82.4 + 84.5) = 141.9 \text{ k}$$

$$R = \frac{M}{a} \Rightarrow a = \frac{M}{R}$$

$$\text{For } \phi M_n = 773.4$$

$$\phi R_n = 141.9$$

$$\text{Then } a = \frac{773.4}{141.9} = 5.5'$$

$$\text{For } a = 5', R = 155.7 \text{ k}$$

$$\text{Ratio} = \frac{141.9}{155.7} = 0.91$$

<u>For a=5'</u>	<u>l</u>	<u>$\phi P_n \times .91$</u>	<u>$= .91 \phi P_n$</u>	<u>ϕP_n</u>
	40	177.9	162	152
	50	173.1	158	147
	60	169.8	155	144
	70	167.7	153	142
	80	166.1	151	140
	90	164.9	150	139

\therefore For $a=5'$, use $a=6'$ values.


Shear Capacity of Pile

Summary of Shear

$$\phi V_n = \phi (V_c + V_s)$$

<u>f'_c</u>	<u>V_c</u>	<u>V_s</u>	<u>ϕV_n</u>
8	82.4	84.5	141.9
7	77.1	84.5	137.4
6	71.4	84.5	132.5

Note: There is no reduction in shear strength due to strand development along the pile.



As 'a' gets smaller, the reaction R (hence, shear V_n) gets larger also. The controlling 'a' distance is different for each f'_c .

(see next page)

Shear Capacity of Section

Per ACI 318-83, Ch. 11, Sec 11.4.2

$$\phi V_n = \phi (V_c + V_s)$$

$$\phi = .85$$


V_s = shear strength provided by the spiral

V_c = shear strength of concrete

$$\underline{V_s} \quad V_s = \frac{A_v f_y d}{s}$$

$$f_y = 60 \text{ ksi}$$

$$d = 24/2 = 12"$$



$$\text{but } d \geq .8h = .8(24) = 19.2" \leftarrow \text{Controls}$$

$$A_v = 2 \times .11 = .22 \text{ in}^2$$

$$s = 3"$$

$$\therefore V_s = \frac{(.22 \times 60 \times 19.2)}{3} = \underline{89.5 \text{ k}}$$

$$\underline{V_c} \quad \text{Lesser of } V_{ci} \text{ of } V_{cw}$$

Because the shear varies for every length pile and load application, use equation

$$V_c = 2\sqrt{f'_c} b d$$

$$b = 24"$$

$$d = 19.2"$$

$$\frac{f'_c \text{ (ksi)}}{V_c \text{ (k)}}$$

$$8 \quad 92.4$$

$$7 \quad 77.1$$

$$6 \quad 71.4$$

$$V_{ci} = .6\sqrt{f_c'} b d + \cancel{V_d} + \frac{V_i M_{cr}}{M_{max}}$$

Let $f_c' = 8000$

$b = 24$

$d = 20.4$

$V_i = R_T = \frac{M}{a} = \frac{778.4 \text{ k-ft}}{a}$

$M_{max} = M = 778.4 \text{ k-ft} \times 12 \text{ in/ft} = 9341 \text{ k-in}$

$M_{cr} = S (.6\sqrt{f_c'} + f_{pc} - \cancel{f_d})$

$f_{pc} = 1.145 \text{ ksi}$

$S = \frac{b h^3}{6} = \frac{24 (24)^3}{6} = 2304$

$\therefore M_{cr} = 2304 (.6\sqrt{\frac{8000}{1000}} + 1.145) = 3875 \text{ k-in}$

$\therefore V_{ci} = .6\sqrt{\frac{8000}{1000}} \cdot 24 \cdot 20.4 + \left(\frac{778.4/a}{9341} \right) \cdot 3875$

$= 26.3 + 322.9/a$ where a is in feet

<u>a</u>	<u>322.9/a</u>	<u>V_{ci}</u>
0	∞	∞
5	64.6	90.9
10	32.3	58.6
15	21.5	47.8
20	16.1	42.4
25	12.9	39.2

But $V_{ci} \geq 1.7\sqrt{f_c'} b d$
 $= 1.7\sqrt{\frac{8000}{1000}} \cdot 24 \cdot 20.4$
 $= \underline{74.4 \text{ k-in}}$

$$V_{cw} = (3.5 \sqrt{f'_c} + .3 f_{pc}) b d + \cancel{V_p} \rightarrow 0$$

$$\text{So } f'_c = 8000$$

$$f_{pc} = f_{pe} = 1.145$$

$$b = 24 \quad d = 19.2$$

$$\therefore V_{cw} = \left(3.5 \sqrt{\frac{8000}{1000}} + .3 \times 1.145 \right) 24 \times 19.2 = \underline{303"}$$

Conclusion

Concrete shear calculated by V_{ci} controls.

$$\underline{f'_c = 8000}$$

$$V_{ci} = 74.4"$$

$$V_s = 84.5"$$

$$\therefore \phi V_n = 0.85 (74.4 + 84.5) = \underline{135"}$$

Using a factor of safety of 1.5 to go from "ultimate nominal capacity" to "service level capacity" to use with the form factor.

$$V_{(allow)} = \frac{V_u}{1.5} \leq \frac{\phi V_n}{1.5} = \frac{135}{1.5} = \underline{90"}$$

check strand
development

This is the maximum allowable shear on the 24" \square pile.

Strand development

The charts that plot ϕP_n vs. L are all based on developing the nominal moment ϕM_n . This moment is defined as the moment corresponding to:

- 1) $\epsilon_c \leq .0021$
- 2) $f_{ps} \leq 240 \text{ ksi}$

In order to obtain a strand stress of f_{ps} , the strand must be fully developed. If the strand development length is less than that provided, ratio down the nominal moment; hence, the allowable reaction.

Per ACI Sec. 12.9


$$l_d = \left(f_{ps} - \frac{2}{3} f_{se} \right) d_b$$

$$f_{ps} = 240 \text{ ksi max.}$$

$$f_{se} = 154 \text{ ksi for stiff pile}$$

$$d_b = 1/2"$$

$$\therefore l_d = \left(240 - \frac{2}{3} \cdot 154 \right) \cdot \frac{1}{2} = \underline{69"} = \underline{5'-9"}$$



f_{ps} is developed when

$$a \geq (5'-9") - (1'-0") = 4'-9"$$

$$\text{Seg } a \geq 5'-0"$$

- Determine the allowable 'a' dimension so that the shear strength is not exceeded. Work backwards, knowing the shear capacity.
 - Find ϕV_n w/ $\phi = .95$
 - Find ϕM_n w/ ϕ determined by $\epsilon_c = .0021$
 - Solve for load location 'a' when both ϕM_n and ϕV_n are both reached simultaneously

f'_c	ϕV_n	$\phi M_n @ \epsilon_c = .0021$	$a = \phi M_n / \phi V_n$
8	141.9	779.4	5.5
7	137.4	749.5	5.4
6	132.5	708.9	5.4

For 'a' less than this distance, the shear capacity of the pile will control.

Example For $f'_c = 9$ ksi: $\phi M_n = 779.4$ k-ft @ $\epsilon_c = .0021$

For 24" \square stiff pile, $\phi V_n = .95(166.9) = 141.9$ k

The corresponding load application point 'a' is

$$a = \frac{M_n}{R} = \frac{M_n}{V_n} = \frac{779.4 \text{ k-ft}}{141.9 \text{ k}} = \underline{5.5'}$$

Develop Equation for Reaction, R

Baseline Case $f'_c = 3 \text{ ksi}$ $L = 65'$ $a = 15'$ $b = 50'$

$$M = \frac{Pab}{L}$$

$M = 778.4 = \text{constant for all lengths for a given } f'_c.$

$$\therefore P = \frac{ML}{ab}$$

<u>L</u>	<u>a</u>	<u>b</u>	<u>Calculated P</u>	<u>FENDER P</u>	<u>Δ</u>
65	15	50	67.5	67.5	0
40	5	35	177.9	177.9	0
90	20	70	50.0	50.0	0

Good! ✓

Conclusion

Therefore; for a given concrete strength f'_c , the reaction at the point of load is a function of L , a and b . It can be solved by statics.

$$P = \frac{ML}{ab} \quad \text{where } P = \text{load}$$

L varies $40'$ to $90'$ by 5

a varies $0'$ to $25'$ by 5

$$b = (L - a)$$

$M =$ controlling moment of cross-section governed

by 1) $\epsilon_c \leq .0021 \text{ in/in}$


2) $f_{sc} \leq 24.0 \text{ ksi}$


Reaction @ top of pile

From statics $R_T = \frac{Pb}{l}$

but $P = \frac{Ml}{ab}$

$\therefore R_T = \left(\frac{Ml}{ab} \right) \cdot \frac{b}{l} = \frac{M}{a} = \text{constant}$





$$P = \frac{Ml}{ab} \quad - \text{load applied}$$

R_T = reaction @ top of pile
= shear in pile

$$\therefore R_T = \frac{Pb}{l} = \frac{M}{a}$$

Possible lengths, l . 40' to 90' by 5

Possible, a 0 to 25' by 5

write program on HP41-CV to generate the values P and R_T .

1) Set 'M' and 'a' as input constants

2) Select first value of l

→ 3) Compute $b = l - a$

4) Calculate $P = Ml/ab$

5) Increment value of l by 5'


6) Repeat step 3)

7) Calculate $R_T = M/a$

$$f'_c = 8000 \text{ psi}$$

$$\text{where } \phi M_n = 778.4 \text{ k-ft}$$

$$P = \frac{M \ell}{ab}$$



Allowable Applied Load, ϕP_n (kips)


ℓ (ft) \ q (k/ft)	0	5	10	15	20	25
40	∞	177.9	103.8	83.0	77.8	83.0
45	\uparrow	175.1	100.1	77.8	70.1	70.1
50		173.1	97.3	74.1	64.9	62.3
55		171.2	95.1	71.4	61.2	57.1
60		169.8	93.4	69.2	58.4	53.4
65		168.7	92.0	67.5	56.2	50.6
70		167.7	90.8	66.0	54.5	48.4
75		166.8	89.8	64.9	53.1	46.7
80		166.1	89.0	63.9	51.9	45.2
85		165.4	88.2	63.0	50.9	44.1
90	\downarrow	164.8	87.6	62.3	50.0	43.1
R (k)	∞	155.7	77.8	51.9	38.9	31.1

$$R = \frac{Pb}{\ell} = \frac{M}{a}, \quad R = \text{constant for given 'a'}$$

$$f'_c = 8000 \text{ psi}$$

$$\text{where } \phi M_n = 773.4 \text{ k-ft}$$

$$P = \frac{M \cdot l}{a \cdot b}$$



~~Allowable~~ Applied Load (ϕP_n) (kips)

$\frac{a}{l}$ (ft)	5.5 ϕ	6	7	8	9	12
40	164.1	152.6	134.8	121.6	111.6	92.7
45	161.2	149.7	131.7	118.3	108.1	89.5
50	159.0	147.4	129.3	115.8	105.5	85.4
55	157.3	145.6	127.4	113.9	103.9	83.0
60	155.3	144.1	125.9	112.3	101.8	81.1
65	154.6	142.9	124.6	111.0	100.4	79.6
70	153.6	141.9	123.6	109.9	99.2	78.3
75	152.7	141.0	122.6	108.9	98.3	77.2
80	152.0	140.3	121.9	108.1	97.5	76.3
85	151.3	139.6	121.2	107.4	96.7	75.5
90	150.7	139.0	120.6	106.8	96.1	74.8
R (k)	141.5	129.7	111.2	97.3	86.5	64.9

$$R = \frac{P \cdot b}{l} = \frac{M}{a}, \quad R = \text{constant for given 'a'}$$

ABAM
CONSULTING ENGINEERS

Project NCEL PHASE V

Sheet 22 of 34

Job No. _____

Designer CWS

Date 6/8/88


Subject 24" Sq. Pile

Allowable Applied Load, P

$$f'_c = 7000 \text{ psi}$$

$$\text{where } M = 749.5 \text{ k-ft}$$

$$P = \frac{M \ell}{ab}$$



Allowable Applied Load, P (kips)


ℓ (ft) \ a (ft)	0	5	10	15	20	25
40	∞	171.1	99.9	79.8	74.9	79.8
45	\uparrow	168.4	96.2	74.9	67.4	67.4
50		166.3	93.6	71.3	62.4	59.9
55		164.7	91.5	68.6	58.8	54.9
60		163.3	89.8	66.5	56.1	51.3
65		162.2	88.5	64.9	54.1	48.7
70		161.2	87.3	63.5	52.4	46.6
75		160.4	86.4	62.4	51.0	44.9
80		159.7	85.5	61.4	49.9	43.5
85		159.1	84.8	60.6	48.9	42.4
90	\downarrow	158.5	84.2	59.9	48.1	41.5
R (k)	∞	149.7	74.9	49.9	37.4	29.9

$$R = \frac{Pb}{\ell} = \frac{M}{a}, \quad R = \text{constant for given 'a'}$$

$$f'_c = 7000 \text{ psi}$$

$$P = \frac{M \ell}{ab}$$

where $M = 748.5 \text{ k-ft}$



Allowable Applied Load, \textcircled{P} (kips)

ℓ (ft)	a (ft)	5.5 ϕ	6	7	8	9	12
40		157.3	146.8	129.6	117.0	107.3	89.1
45		↑ 155.0	143.9	126.6	113.8	104.0	85.1
50		152.9	141.8	124.3	111.4	101.4	82.1
55		151.2	140.0	122.5	109.5	99.4	79.8
60		149.3	138.6	121.1	108.0	97.8	78.0
65		149.7	137.4	119.8	106.7	96.5	76.5
70		147.7	136.4	118.8	105.6	95.4	75.3
75		146.9	135.6	117.9	104.7	94.5	74.3
80		146.1	134.9	117.2	104.0	93.7	73.4
85		145.5	134.2	116.5	103.3	93.0	72.6
90		√ 144.9	133.7	115.9	102.7	92.4	72.0
R (k)		136.1	124.8	106.9	93.6	83.2	62.4

$$R = \frac{Pb}{\ell} = \frac{M}{a}, \quad R = \text{constant for given 'a'}$$

ABAM
CONSULTING ENGINEERS

Project NCEL PHASE V

Sheet 24 of 34

Job No. _____

Designer CWS

Date 6/8/83


Subject 24" Sq. Pile

Allowable Applied Load, P

$$P'_c = 6000 \text{ psi}$$

$$P = \frac{M \cdot l}{a \cdot b}$$

$$\text{where } M = 708.9 \text{ k-ft}$$



Allowable Applied Load, P (kips)


$\frac{a}{l}$ (ft)	0	5	10	15	20	25
40	∞	162.0	94.5	75.6	70.9	75.9
45	\uparrow	159.5	91.1	70.9	63.8	63.8
50		157.5	88.6	67.5	59.1	56.7
55		156.0	86.6	65.0	55.7	52.0
60		154.7	85.1	63.0	53.2	48.6
65		153.6	83.8	61.4	51.2	46.1
70		152.7	82.7	60.1	49.6	44.1
75		151.9	81.8	59.1	48.3	42.5
80		151.2	81.0	58.2	47.3	41.2
85		150.6	80.3	57.4	46.4	40.2
90	\downarrow	150.1	79.8	56.7	45.6	39.3
R (k)	∞	141.8	70.9	47.3	35.4	28.4

$$R = \frac{P \cdot b}{l} = \frac{M}{a}, \quad R = \text{constant for given 'a'}$$

$$f'_c = 6000 \text{ psi}$$

$$P = \frac{M \ell}{ab}$$

where $M = 708.9 \text{ k-ft}$



Allowable Applied Load, P (kips)


$\begin{matrix} a \\ (ft) \\ \swarrow \\ \ell \\ (ft) \end{matrix}$	$\begin{matrix} 5.5 \\ \phi \end{matrix}$	6	7	8	9	12
40	149.4	139.0	122.8	110.8	101.6	89.4
45	\uparrow 146.3	136.3	119.9	107.9	98.5	80.6
50	144.3	134.3	117.8	105.5	96.1	77.7
55	143.2	132.6	116.0	103.7	94.2	75.6
60	141.9	131.3	114.6	102.2	92.7	73.8
65	140.3	130.2	113.5	101.0	91.4	72.5
70	139.9	129.2	112.5	100.0	90.4	71.3
75	139.1	128.4	111.7	99.2	89.5	70.3
80	138.4	127.7	111.0	98.5	88.8	69.5
85	137.8	127.1	110.4	97.8	88.1	68.8
90	\downarrow 137.3	126.6	109.8	97.3	87.5	68.2
R (k)	128.9	118.2	101.3	88.6	78.8	59.1

$$R = \frac{Pb}{\ell} = \frac{M}{a}, \quad R = \text{constant for given 'a'}$$

$f'_c = \underline{000 \text{ psi}}$

$P = \frac{M \cdot l}{ab}$


where $M = \underline{\hspace{2cm}} \text{ ft-k}$



Allowable Applied Load, \textcircled{P} (kips)

$\begin{matrix} a \\ (ft) \end{matrix} \backslash \begin{matrix} l \\ (ft) \end{matrix}$	0	6	7	8	9	12
40	∞					
45	\uparrow					
50						
55						
60						
65						
70						
75						
80						
85						
90	\downarrow					
R (k)	∞					

$\checkmark \quad R = \frac{Pb}{l} = \frac{M}{a}, \quad R = \text{constant for given 'a'}$



Note: For $\alpha < 6'$, Further investigation must be made considering both shear and spiral development

BE for 4E80

Find the "equivalent" ϕ factor

Rather than multiplying the nominal strength of the pile at a strain of .003 in/in by $\phi = 0.9$, an equivalent ϕ was used. This ϕ was determined by using the design strength when the pile is at a strain of .003 in/in.

$f'_c = 8 \text{ ksi}$

$M @ \epsilon = .003 \text{ in/in} = M_n$

$M_n = 826.8 \text{ k-ft}$

$M @ \epsilon = .0021 \text{ in/in} = \phi M_n$

$\phi M_n = 778.4 \text{ k-ft}$

$\therefore \text{Equivalent } \phi = \frac{\phi M_n}{M_n} = \frac{778.4}{826.8} = .94$

$\text{Equiv. } \phi = .94$

PROJECT: NCEL FENDER SYSTEM STUDY W/ 24" PILES
 DATE: 6/8/88
 DESIGNER: CWS
 PROGRAM: 'FENDER' DEVELOPED BY ABAM ENGR. INC.

DATA FILE: B:24STIFF.DAT
 PILE NUMBER: 24" SQ. W/ RECT. STRAND PAT. & $f'c = 8$
 REVISION #: 0
 REMARKS: 28 STRANDS W/ 8/6/0 PAT.

PILE DIMENSIONS:

LENGTH = 65 ft = L
 LOAD FROM TOP = 15 ft = a
 DEPTH = 24 in
 WIDTH = 24 in

CONCRETE DATA:

STRENGTH $f'c$ = 8 ksi
 MODULUS E = 4577 ksi
 PRESTRESS fpc = 1145 psi

STRAND DATA:

STRAND TYPE = LOW RELAXATION
 # STRANDS = 28
 STRESS fpu = 270 ksi
 STRESS fse = 154 ksi
 MODULUS E = 28000 ksi
 AREA = 1.224 sq.in DEPTH = 2.75 in
 AREA = .918 sq.in DEPTH = 4.75 in
 AREA = 0 sq.in DEPTH = 6.75 in
 AREA = 0 sq.in DEPTH = 17.25 in
 AREA = .918 sq.in DEPTH = 19.25 in
 AREA = 1.224 sq.in DEPTH = 21.25 in

MOMENT Mn (K-ft)	CURVATURE (rad/in)	CONC STRAIN (in/in)	UPPER STRAND STRESS (ksi)	LOWER STRAND STRESS (ksi)	NA DEPTH (in)
234.8	2.085E-05	0.00050	-148.6	-159.4	24.00
374.4	4.050E-05	0.00070	-144.5	-165.5	17.27
466.3	6.578E-05	0.00090	-140.9	-174.9	13.68
541.3	9.559E-05	0.00110	-137.6	-187.1	11.51
610.3	1.290E-04	0.00130	-134.5	-201.4	10.08
676.5	1.654E-04	0.00150	-131.7	-216.9	9.07
725.5	2.032E-04	0.00170	-129.1	-227.9	8.36
754.8	2.415E-04	0.00190	-126.4	-235.2	7.87
778.4	2.803E-04	0.00210	-123.8	-240.4	7.49
794.2	3.194E-04	0.00230	-121.2	-244.3	7.20
806.2	3.588E-04	0.00250	-118.6	-247.4	6.97
815.7	3.986E-04	0.00270	-116.1	-249.8	6.77
823.4	4.387E-04	0.00290	-113.6	-251.7	6.61
826.8	4.589E-04	0.00300	-112.3	-252.6	6.54

100 - 34

* DATA FILE: B:24STIFF.DAT
 * PILE NUMBER: 24" SQ. W/ RECT. STRAND PAT. & f'c = 8
 * REVISION #: 0
 REMARKS: 28 STRANDS W/ 8/6/0 PAT.

MOMENT Mn (k-ft)	CONC STRAIN (in/in)	ENERGY (k-ft)	LOAD (kips)	DEFLECTION (in)
234.8	0.00050	0.6	20.3	0.8
374.4	0.00070	2.0	32.5	1.4
466.3	0.00090	3.7	40.4	1.9
541.3	0.00110	6.1	46.9	2.6
610.3	0.00130	9.2	52.9	3.3
676.5	0.00150	13.3	58.6	4.2
725.5	0.00170	17.1	62.9	5.0
756.8	0.00190	20.2	65.6	5.5
778.4	0.00210	22.8	67.5	6.0
794.2	0.00230	25.1	68.8	6.4
806.2	0.00250	27.2	69.9	6.8
815.7	0.00270	29.0	70.7	7.1
823.4	0.00290	30.7	71.4	7.4
826.8	0.00300	31.5	71.7	7.5

PROJECT: NCEL FENDER SYSTEM STUDY W/ 24" PILES
 DATE: 6/8/88
 DESIGNER: CWS
 PROGRAM: 'FENDER' DEVELOPED BY ABAM ENGR. INC.

DATA FILE: B:24STIFF.DAT
 PILE NUMBER: 24" SQ. W/ RECT. STRAND PAT. & $f'c = 7$
 REVISION #: 0
 REMARKS: 28 STRANDS W/ 8/6/0 PAT.

PILE DIMENSIONS:

LENGTH = 65 ft = L
 LOAD FROM TOP = 15 ft = a
 DEPTH = 24 in
 WIDTH = 24 in

CONCRETE DATA:

STRENGTH $f'c$ = 7 ksi
 MODULUS E = 4346 ksi
 PRESTRESS fpc = 1145 psi

STRAND DATA:

STRAND TYPE = LOW RELAXATION
 # STRANDS = 28
 STRESS fpu = 270 ksi
 STRESS fse = 154 ksi
 MODULUS E = 28000 ksi
 AREA = 1.224 sq.in DEPTH = 2.75 in
 AREA = .918 sq.in DEPTH = 4.75 in
 AREA = 0 sq.in DEPTH = 6.75 in
 AREA = 0 sq.in DEPTH = 17.25 in
 AREA = .918 sq.in DEPTH = 19.25 in
 AREA = 1.224 sq.in DEPTH = 21.25 in

MOMENT Mn (K-ft)	CURVATURE (rad/in)	CONC STRAIN (in/in)	UPPER STRAND STRESS (ksi)	LOWER STRAND STRESS (ksi)	NA DEPTH (in)
235.6	2.196E-05	0.00053	-148.3	-159.7	24.00
356.1	3.856E-05	0.00070	-144.7	-164.7	18.16
449.9	6.272E-05	0.00090	-141.0	-173.5	14.35
525.0	9.135E-05	0.00110	-137.6	-184.9	12.04
593.1	1.236E-04	0.00130	-134.5	-198.5	10.52
654.5	1.577E-04	0.00150	-131.5	-213.2	9.51
698.0	1.913E-04	0.00170	-128.5	-224.1	8.89
727.5	2.252E-04	0.00190	-125.5	-231.6	8.44
748.5	2.596E-04	0.00210	-122.6	-237.0	8.09
764.3	2.943E-04	0.00230	-119.6	-241.2	7.81
776.6	3.294E-04	0.00250	-116.7	-244.5	7.59
786.5	3.649E-04	0.00270	-113.9	-247.1	7.40
794.7	4.008E-04	0.00290	-111.0	-249.3	7.24
798.3	4.188E-04	0.00300	-109.6	-250.2	7.16

* DATA FILE: B:24STIFF.DAT
 * PILE NUMBER: 24" SQ. W/ RECT. STRAND PAT. & f'c = 7
 * REVISION #: 0
 REMARKS: 28 STRANDS W/ 8/6/0 PAT.

MOMENT Mn (k-ft)	CONC STRAIN (in/in)	ENERGY (k-ft)	LOAD (kips)	DEFLECTION (in)
235.6	0.00053	0.7	20.4	0.8
356.1	0.00070	1.8	30.9	1.3
449.9	0.00090	3.4	39.0	1.9
525.0	0.00110	5.6	45.5	2.5
593.1	0.00130	8.6	51.4	3.2
654.5	0.00150	12.2	56.7	4.0
698.0	0.00170	15.4	60.5	4.7
727.5	0.00190	18.1	63.0	5.2
748.5	0.00210	20.4	64.9	5.6
764.3	0.00230	22.5	66.2	6.0
776.6	0.00250	24.4	67.3	6.4
786.5	0.00270	26.2	68.2	6.7
794.7	0.00290	27.8	68.9	7.0
798.3	0.00300	28.6	69.2	7.1

PROJECT: NCEL FENDER SYSTEM STUDY W/ 24" PILES
 DATE: 6/8/88
 DESIGNER: CWS
 PROGRAM: 'FENDER' DEVELOPED BY ABAM ENGR. INC.

DATA FILE: B:24STIFF.DAT
 PILE NUMBER: 24" SQ. W/ RECT. STRAND PAT. & $f'_c = 6$
 REVISION #: 0
 REMARKS: 28 STRANDS W/ 8/6/0 PAT.

PILE DIMENSIONS:

LENGTH = 65 ft = L
 LOAD FROM TOP = 15 ft = a
 DEPTH = 24 in
 WIDTH = 24 in

CONCRETE DATA:

STRENGTH f'_c = 6 ksi
 MODULUS E = 4098 ksi
 PRESTRESS f_{pc} = 1145 psi

STRAND DATA:

STRAND TYPE = LOW RELAXATION
 # STRANDS = 28
 STRESS f_{pu} = 270 ksi
 STRESS f_{se} = 154 ksi
 MODULUS E = 28000 ksi

AREA = 1.224 sq.in DEPTH = 2.75 in
 AREA = .918 sq.in DEPTH = 4.75 in
 AREA = 0 sq.in DEPTH = 6.75 in
 AREA = 0 sq.in DEPTH = 17.25 in
 AREA = .918 sq.in DEPTH = 19.25 in
 AREA = 1.224 sq.in DEPTH = 21.25 in

MOMENT M_n (k-ft)	CURVATURE (rad/in)	CONC STRAIN (in/in)	UPPER STRAND STRESS (ksi)	LOWER STRAND STRESS (ksi)	NA DEPTH (in)
236.5	2.329E-05	0.00056	-148.0	-160.0	24.00
334.4	3.642E-05	0.00070	-145.0	-163.9	19.22
430.8	5.939E-05	0.00090	-141.2	-172.0	15.16
506.3	8.673E-05	0.00110	-137.7	-182.6	12.68
572.7	1.174E-04	0.00130	-134.5	-195.3	11.07
622.3	1.479E-04	0.00150	-131.2	-207.8	10.14
660.1	1.774E-04	0.00170	-127.9	-218.7	9.58
688.1	2.070E-04	0.00190	-124.6	-226.5	9.18
708.9	2.369E-04	0.00210	-121.3	-232.3	8.87
725.0	2.672E-04	0.00230	-118.0	-236.8	8.61
737.8	2.979E-04	0.00250	-114.8	-240.5	8.39
748.4	3.289E-04	0.00270	-111.6	-243.4	8.21
757.4	3.604E-04	0.00290	-108.4	-245.9	8.05
761.3	3.762E-04	0.00300	-106.8	-246.9	7.97

24 - 24

* DATA FILE: B:24STIFF.DAT
* PILE NUMBER: 24" SQ. W/ RECT. STRAND PAT. & f'c = 6
* REVISION #: 0
REMARKS: 28 STRANDS W/ 8/6/0 PAT.

MOMENT Mn (k-ft)	CONC STRAIN (in/in)	ENERGY (k-ft)	LOAD (kips)	DEFLECTION (in)
236.5	0.00056	0.7	20.5	0.8
334.4	0.00070	1.6	29.0	1.2
430.8	0.00090	3.1	37.3	1.8
506.3	0.00110	5.2	43.9	2.4
572.7	0.00130	7.9	49.6	3.1
622.3	0.00150	10.6	53.9	3.7
660.1	0.00170	13.2	57.2	4.3
688.1	0.00190	15.6	59.6	4.8
708.9	0.00210	17.7	61.4	5.2
725.0	0.00230	19.6	62.8	5.6
737.8	0.00250	21.4	63.9	5.9
748.4	0.00270	23.1	64.9	6.2
757.4	0.00290	24.6	65.6	6.5
761.3	0.00300	25.4	66.0	6.7

DISTRIBUTION LIST

DTIC Alexandria, VA
GIDEP OIC, Corona, CA
NAS Code 110, Adak, AK; PW Engrg (Branson), Patuxent River, MD; SCE, Alameda, CA
NAVFACENGCOM Code 03, Alexandria, VA; Code 04, Alexandria, VA; Code 04A3, Alexandria, VA; Code 10, Alexandria, VA
NAVFACENGCOM - CHES DIV, FPO-IPL, Washington, DC
NAVFACENGCOM - LANT DIV, Code 04, Norfolk, VA; Library, Norfolk, VA
NAVFACENGCOM - NORTH DIV, Code 04, Philadelphia, PA; Code 04AL, Philadelphia, PA; Code 408AF, Philadelphia, PA
NAVFACENGCOM - PAC DIV, Code 04, Pearl Harbor, HI; Library, Pearl Harbor, HI
NAVFACENGCOM - SOUTH DIV, Code 04, Charleston, SC; Library, Charleston, SC
NAVFACENGCOM - WEST DIV, Code 04, San Bruno, CA; Code 111, San Bruno, CA; Code 402, San Bruno, CA; Code 04A2.2 (Lib), San Bruno, CA
NAVPHIBASE Code 432 (Turner), Norfolk, VA
NAVSTA SCE, Charleston, SC; SCE, Guam, Marianas Islands; SCE, Norfolk, VA; SCE, Pearl Harbor, HI; SCE, San Diego, CA
NAVBASE Fac Plng & Prog, San Francisco, CA
NMCB 133, H-CO S3E (Engrg Dept)
PWC CO, Guam, Mariana Islands; CO, Norfolk, VA; CO, Oakland, CA; CO, Pearl Harbor, HI; Code 101 (Library), Oakland, CA; Code 110, San Diego, CA; Code 123-C, San Diego, CA; Code 400, Oakland, CA; Code 420, Great Lakes, IL; Code 700, Great Lakes, IL; Library (Code 134), Pearl Harbor, HI; Library, Guam, Mariana Islands; Library, Norfolk, VA; Library, Pensacola, FL; Library, Yokosuka, Japan; Code 421, Pearl Harbor, HI; Tech Library, Subic Bay, RP
FLORIDA INST OF TECH G, Swain, Melbourne, FL
SEATTLE UNIVERSITY CE Dept (Schwaegler), Seattle, WA
TEXAS A&M UNIVERSITY CE Dept (Machemehl), College Station, TX
ALVIN ZANE & ASSOC, INC Honolulu, HI
COLLINS ENGRG, INC M Garlich, Chicago, IL
CURTIS ENGRG CORP DH Curtis, National City, CA
GEOTECHNICAL ENGRS, INC Murdock, Winchester, MA
INTL MARITIME, INC D Walsh, San Pedro, CA
LEO A DALY CO Honolulu, HI
MC CLELLAND ENGRS, INC Library, Houston, TX
MOFFATT & NICHOL ENGRS WS Shipple, Long Beach, CA
PACIFIC MARINE TECH (M. Wagner) Duvall, WA
PRESNELL ASSOC, INC DG Presnell, Jr, Louisville, KY
STAN'S RAND Grismala, Ogden, UT